

REPORT NO. 5059B

MM&TE - APPLICATION OF RADAR TO BALLISTIC ACCEPTANCE TESTING OF AMMUNITION (ARBAT) PHASE B: ANTENNA DEVELOPMENT/FABRICATION

FINAL REPORT (PHASE B)
CDRL: A002

30 September 1976

SARPA-QA-A-R

PICATINNY ARSENAL DOVER, NEW JERSEY 07801

DRCMS CODE: 4932.05.4139.1

CONTRACT NO. DAAA21-73-C-0664

See 1473

Distribution of the document is unlimited.

The findings in this report are not to be construed as an official Department of Army position.

Destroy this report when no longer needed. Do not return it to the originator.

7821 Orion Avenue
Van Nuys, California 90406

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

AD	

REPORT NO. 5059B

MM&TE - APPLICATION OF RADAR TO BALLISTIC ACCEPTANCE TESTING OF AMMUNITION (ARBAT) PHASE B: ANTENNA DEVELOPMENT/FABRICATION

FINAL REPORT (PHASE B)

CDRL: A002

30 September 1976

SARPA-QA-A-R



PICATINNY ARSENAL DOVER, NEW JERSEY 07801


DRCMS CODE: 4932.05.4139.1 CONTRACT NO. DAAA21-73-C-0664

Distribution of the document is unlimited.

The findings in this report are not to be construed as an official Department of Army position.

Destroy this report when no longer needed. Do not return it to the originator.

ITT GILFILLAN 7821 Orion Avenue Van Nuys, California 90406



ABSTRACT

The ARBAT (Application of Radar to Ballistic Acceptance Testing of Ammunition) radar system is presently being developed by Picatinny Arsenal for range instrumentation purposes. This report covers the development of the antenna subsystem through range testing of a 9-element test array and assembly of the full antenna. The subject antenna is a 10 x 12 ft phase/frequency/mechanical scanning X-band planar array. Elevation scanning is by means of phase variation obtained by program controlled 4-bit diode phase shifters. In addition to the electronic scanning capability, a manual tilt capability is included to accommodate range terrain variations. Azimuth scanning is accomplished by frequency variation, and limited mechanical rotation of the array by servo control. Mechanical rotation is limited to ±170 degrees which fulfills the requirements of the application. The transmitter/receiver unit is mounted on the antenna back structure. Connections to and from the transmitter/receiver and phase shifter control electronics are made through a "windup" cable arrangement eliminating the need for slip rings. The array is made up of 167 horizontal dual-slot pair radiators fed by a vertical feed line.

The antenna incorporates a performance monitoring feature which functions as a confidence indicator and as a means for fault location down to the single horizontal array level. This feature is implemented by means of coupling each horizontal array, opposite the feed end, to a vertical combiner, or performance monitor line. Residual RF energy in the radiating sections is combined and detected to monitor array performance. Simple diagnostic phase shifter exercising programs facilitate fault location.

ACCOUNTS TABLE CONTESS

BY

CITED AND APPRICATE CONESS

BILL AND APPRICATE CONESS

BILL AND APPRICATE CONESS

FOREWORD

ARBAT PHASE B (FABRICATION AND TESTING OF A PHASED ARRAY FREQUENCY SCAN RADAR ANTENNA)

The subject report covers the second phase (antenna fabrication and testing) of a multiple phase program to develop and deliver an X-band phase/frequency/mechanical scanning radar for ballistic ammunition testing applications.

Related data contained in this report concerns the intermediate steps of test element and test array fabrication, and testing of those components individually, then as a nine element test array on the test range.

In addition to the detailed specific requirements placed on the antenna design/implementation, there is an obvious requirement for complete compatibility with the other radar group elements to insure achievement of the overall radar system performance specifications when the subject antenna is assembled into the system.

Where useful in describing the development of the antenna, non-scale sketches have been used in some instances to clarify the text only. Photographs of the assembled antenna are included.

The report presents data collected during the course of the Phase B design and fabrication, and data pertinent to the testing program through the nine element test array range pattern measurement activities.

TABLE OF CONTENTS

Section			Page
	ABST	RACT	iii
	FORE	WORD	v
1.	DEVE	LOPMENT APPROACH	1
	1.1	Overall Characteristics	1
		1.1.1 General Description	1
	1.2	Detailed Requirements	9
2.	DESIG	ON DESCRIPTIONS	18
	2.1	Back Structure Horizontal Array Waveguide Secti	19 ons 24
	2.3	Vertical Feed Line	35
	2.4	90 Degree Twist Crossguide Coup	ler Section 40
		2.4.1 Load: Termination (Ver	
		Coupler) 2.4.2 Phase Randomization Blo	ocks 46
	2.5	Diode Phase Shifter ARBAT Antenna Performance Mo	51 nitor Concept 54
	2.6		
		2.6.1 Performance Monitor Li 2.6.2 Loads: Performance Mo	
3.	TEST	PROGRAM	63
	3.1	Short Array (3 Section) Tests	63
	3.2	Nine-Element Test Array	68
		3.2.1 Test Patterns	69
4.	SUMN	MARY OF TEST RESULTS	82
	APPE	NDIX A	83
	REPO	ORT DISTRIBUTION	105
	REPO	ORT DOCUMENTATION PAGE	109

LIST OF ILLUSTRATIONS

Figure		Page
1.	ARBAT Phase Antenna Development Sequence	2
2.	System Configuration Concept	4
3.	Back Structure/Transceiver Mounting	5
4.	Antenna Signal Flow Graphic Schematic	6
5.	Antenna Assembly Front Array View	7
6.	Antenna Assembly Rear View	8
7.	Back Structure Truss Elements	21
8.	Back Structure/Transceiver Mounting	22
9.	Computer Deflection Analysis	23
10.	Insertion Phase Measurement/Comparison Test Setup	26
11.	Insertion Phase Plot (After Etching Process)	27
12.	Phase Error Plot (2nd Aperture Excitation at 9.3 GHz)	29
13.	Phase Error Plot (2nd Aperture Excitation at 9.65 GHz)	30
14.	Phase Error Plot (3rd Aperture Excitation at 10 GHz)	31
15.	Amplitude Plot (1st Aperture Excitation at 9.65 GHz)	32
16.	Amplitude Plot (2nd Aperture Excitation at 9.3 GHz)	33
17.	Amplitude Plot (3rd Aperture Excitation at 20 GHz)	34
18.	Vertical Line Feed in Assembled Antenna	36
19.	Vertical Line Feed Insertion Loss vs Frequency	37
20.	VSWR vs Frequency: Line Feed Section #3	38
21.	VSWR vs Frequency: Line Feed Section #3 (Expanded Scale)	39
22.	Ninety Degree Twist Crossguid Coupler in Assembled	
	Antenna	41
23.	Ninety Degree Twist Crossguide Section	42
24.	Ninety Degree Twist Section VSWR Plot	43
25.	Load: Vertical Feed Coupler VSWR Plot	45
26.	Phase Randomization Block Location in Coupler	47
27.	Phase Randomization Block Series	48
28.	Phase Randomization Block	49
29.	Phase Randomization Block	50
30.	Phase Shifter Decode Logic Organization	52
31.	Phase Shifter Position in Assembled Antenna	53
32.	Performance Monitoring Concept	55
33.	Performance Monitor Slot Dimensions	57
34.	Slot Coupling Values	58
35.	Performance Monitor Line in Assembled Antenna	59
36.	Performance Monitor Line (Close-Up View)	60
37.	Load Block VSWR Measurement	62

LIST OF ILLUSTRATIONS (Continued)

Figure		Page
38.	Horizontal Array Element Insertion Loss (Dual Slot	
	Radiators)	64
39.	Horizontal Array Element Return Loss (Dual Slot	
	Radiators)	65
40.	D-2 Horizontal Array Element Return Loss	
	(Expanded D2 RL)	66
41.	Predicted Pattern (3 Element Test)	67
42.	Nine-Element Test Array Assembly	69
43.	Nine-Element Test Array Assembled	70
44.	Nine-Element Test Array Elevation Scan	71
45.	ARBAT 9-Element Test Array Pattern (9.30)	72
46.	ARBAT 9-Element Test Array Pattern (9.65)	73
47.	ARBAT 9-Element Test Array Pattern (10.0)	74
48.	ARBAT 9-Element Test Array Pattern (9.3)	75
49.	ARBAT 9-Element Test Array Pattern (9.65)	76
50.	ARBAT 9-Element Test Array Pattern (10.0)	77
51.	ARBAT 9-Element Test Array Pattern (9.3)	78
52.	ARBAT 9-Element Test Array Pattern (9.65)	79
53.	ARBAT 9-Element Test Array Pattern (10.0)	80
54.	ARBAT 9-Element Test Array Pattern (9.65)	81

ARBAT ANTENNA

1. DEVELOPMENT APPROACH

0

0

0


0

8

The ARBAT system required the development of an antenna to meet the unique performance requirements of ballistic ammunition testing. The approach followed for this development was standard in antenna design; a paper design was first generated by means of computer analyses. Input data for these analyses were based on proven design parameters generated for similar antennas produced for other programs. An iterative process, in which a single element followed by multiple horizontal array elements were fabricated, tested and modified as necessary to optimize configuration, was followed. A detailed illustration of the development/fabrication sequence followed with the ARBAT antenna is shown in Figure 1.

1.1 Overall Characteristics

1.1.1 General Description. - The antenna is a planar array design with an aperture of 10 ft x 12 ft. Beam scanning is accomplished by a combination of electronic and mechanical means. The beam is scanned in elevation by four-bit diode phase shifters (GFE), whereas azimuth scanning is by frequency variation and mechanical rotation of the array. The mechanical rotation capability is limited to a maximum of ±170 degrees which fulfills the requirements in ammunition testing applications. Provisions are included in the antenna back structure design for a mechnical adjustment (tilt) of 0 to 25 degrees in elevation. The back structure is designed to support the microwave assembly, phase shifter power supplies and logic, and the transmitter/receiver unit. In view of the less than 360 degree rotation required (±1700), a cable "windup" scheme is used for power and all input/output lines to and from the antenna which obviates the need for slip rings. The artists sketch in Figure 2 illustrates the overall system configuration concept. A more detailed view illustrating the back structure concept is shown in Figure 3. The array contains 167 dual slot horizontal radiators which are fed by a single vertical feed line via 90-degree waveguide twist and offset sections followed by 4-bit diode phase shifters. The arrays terminate at a vertical performance monitor line at the end opposite the feed line. The performance monitor line is a part of the performance monitor and fault location feature incorporated in the system design. Antenna performance determination is accomplished by the measurement of residual RF energy at the extreme ends of the horizontal arrays (opposite the feed ends). Coupling from the vertical feed line to the arrays and from the arrays to the performance monitor line is by 4-port coupler



)

Figure 1. ARBAT Phase Antenna Development Sequence

NOTES TO FIGURE 1

NOTE 1:

0

0

Fabrication of "dummy" phase shifter waveguide sections with Rexolite phase shifting block inserts for substitution in place of the diode phase shifters which were not available at the time the tests were required. The Rexolite blocks provide a step transformer with a maximum VSWR of 1.1:5. The phase shift increments of the Rexolite block/waveguide section units were adjusted to ±3 degrees by the application of dielectric tape directly to the side of the block; phase shift was then measured at center frequency.

NOTE 2:

A nine element test array was assembled using the array elements, short feed, waveguide twist sections, dummy phase shifter blocks and couplers prepared earlier. These elements were assembled into a test support to simulate the final full array configuration except with a reduced number of array elements. This test assembly was then moved to the test range for the tests described later in this report.




Figure 2. System Configuration Concept





Figure 3. Back Structure/Transceiver Mounting

sections. Coupling sections at the feed end contain end loads and phase randomization blocks. The 4-port couplers at the performance monitor line section are designed with a common flange which mates with the individual flanges at the output ends of each horizontal array element. The performance monitor feature is implemented by terminating the lower end of the vertical performance monitor line section with a crystal video detector whose output is routed via coaxial cable to the monitoring circuitry. A pictorial drawing showing microwave element configuration and signal flow illustrates the basic antenna physical design, Figure 4.

The two photographs following show the assembled antenna microwave section. The front side showing the horizontal array elements, Figure 5; and the rear of the assembly showing back structure details, vertical feed line, 90 degree twist waveguide sections, and phase shifters is shown in Figure 6.



2

Þ

2

3

Figure 4. Antenna Signal Flow Graphic Schematic




Figure 5. Antenna Assembly Front Array View




Figure 6. Antenna Assembly Rear View

1.2 Detailed Requirements

The following extracts from Appendix A of the contract Statement of Work, include the basic performance requirements placed on the antenna to be achieved when mounted on a suitable pedestal with servo control and when coupled to the modified GFE transmitter for which the antenna has been designed. Pedestal assembly and transceiver modifications are parts of forthcoming program phases.

- 1.0 Beam Steering
- 1.1 Electrical
- 1.1.1 Azimuth: 7.7 degrees minimum
- 1.1.2 Elevation: ±35 degrees minimum
- 1.2 Mechanical
- 1.2.1 Azimuth: ±170 degrees rotation minimum at 40 degrees/sec² while maintaining pointing accuracy during rotation.

The electrical beam motion shall be accomplished with diode phase shifters in elevation and with frequency scanned slotted waveguide radiators in azimuth. The antenna shall be designed for electrical sequential lobing. Provision shall be made for a mechanical adjustment capability in elevation. The angle between the horizontal position and the beam normal of the antenna shall have an adjustable range of 0 to 25°.

2.0	Electrical Requ	uirements	
2.1	Detailed Specif	ication	
2.1.1	Frequency Band	d - X	
2.1.2	Center Frequen	ncy - See Note 1	
2.1.3	Bandwidth for l	Frequency Scan - See	Note 1
2.1.4	Azimuth Scan (Electrical): 7.70	
2.1.5	Elevation Scan	(Electrical): ±35°	
2.1.6	Bandwidth, 3 d	B (Note 2)	
	Azimuth	for 0° elevation for ±35° elevation	.55° .67°
	Elevation	for 0° elevation for ±35° elevation	.66° .81°
2.1.7	Beam Pointing	Error, Electrical	
	Elevation		.37 mrad
2.1.8	Electronic Bear in Elevation	m Switching Time	1.0 MHz
2.1.9	Polarization		Horizontal

NOTE 1: As stated in antenna design specification. (Contract DAAA21-72-C-0725)

2.1.10 Sidelobe Level (Note 2)

Azimuth	at 0° elev. scan	-25 dB
	at ±35° elev. scan	-23 dB
Elevation	at 0° elev. scan	-25 dB
	at ±350 elev. scan	-23 dB

2.1.11 Terminal Gain at 0° Elev. scan at Center Frequency

46.0 minimum (Note 3)

Terminal Gain at ±35° Elev. scan at Center Frequency

45.0 dB (Note 3)

2.1.12 Power Capability

peak 30 kw average 300 w

- 2.2 Major Subassemblies
- 2.2.1 For description and characteristics of GFE phase shifters see Picatinny Arsenal Document Technical Description TDPA-QAAR-2340.
- 2.3 Techniques Used
- 2.3.1 Wideband Operation for Frequency Scan

Appropriate techniques shall be applied to suppress the grating lobes and improve the radiation pattern while operating over the maximum bandwidth necessary for the frequency scan in azimuth.

2.3.2 Phase Randomization

0

To avoid the quantization error of the 4-bit phase shifter and the associated increase in sidelobe level, an appropriate phase randomization technique shall be used for each element of the horizontal array. The antenna buffer shall be able to compensate for this additional insertion phase.

NOTE 2: These parameters will be achieved at the center frequency.

NOTE 3: Based on an average phase shifter insertion loss of 2.5 dB.

2.3.3 Signal Coupling

To generate an optimum pencil beam with the most efficient low sidelobe pattern, proper weighting (30 dB Taylor excitation (N=4)) shall be applied by specifying appropriate coupling apertures from the vertical feed to the horizontal arrays and in establishing the slots in the horizontal elements.

2.3.4 CW Mode

The requirements for a CW mode of operation, to be added in the future, should be considered during the fabrication and design modifications of the antenna.

- 2.3 Mechanical Requirements
- 2.3.1 General Mechanical Requirements
- 2.3.1.1 The antenna array and its supporting structure shall be of sufficient rigidity and strength to minimize the deflection when subjected to the required acceleration and wind loading. When assembled on an appropriate servo mount pedestal (AN/SPS-48 or equivalent) and when subjected simultaneously to 40°/sec² acceleration in azimuth and 20 mph wind load, the antenna system shall exhibit no more than the following maximum deflection of the beam:

BASIC ANTENNA ANTENNA + PEDESTAL (PHASE B) + VEHICLE (PHASE C)

2

- a. Azimuth .377 mrad max. .660 mrad max.
- b. Elevation . 184 mrad max. . . 690 mrad max.
- 2.3.1.2 The antenna shall be properly designed, fabricated and assembled to permit electrical and mechanical operation in accordance with this and the complete ARBAT radar system specifications when subjected to the environmental conditions specified in paragraph 2.8.

In a non-operative state, the antenna system shall be sufficiently rugged to withstand, without damage, vibration and shock during transportation per paragraphs 2.7 and 2.8, and wind loads and precipitation per paragraph 2.8.

- 2.3.2 Detailed Mechanical Specifications
- 2.3.2.1 Antenna Aperture Size: Height 120 ins.
 Width 144 ins.
- 2.3.2.2 Total Antenna Width 154 ins. (ref)
- 2.3.2.3 Adjustable Elevation Tilt 0 to 25°
- 2.3.2.4 Mechanical Pointing Accuracy
 (deflection error due to all
 loading, see para 2.3.1.1) az .377 mrad max.
 el .184 mrad max.
- 2.3.2.5 Maximum Weight (Antenna, transceiver, buffer, power supplies, cables) without pedestal 1700 lbs. max
- 2.3.3 Antenna Microwave Hardware

The antenna shall include, but not be limited to, the following microwave hardware:

- 2.3.3.1 Vertical Feed Line
- 2.3.3.2 90° Waveguide Twist (167)
- 2.3.3.3 Diode Phase Shifters (167)
- 2.3.3.4 Mounting Plate(s) for Phase Shifters
- 2.3.3.5 Horizontal Slotted Array Element (167)
- 2.3.3.6 Required coupling Elements, straight and angular (167 each)
- 2.3.4 Mechanical Mounting Structure

The microwave elements shall be securely mounted to a back structure.

2.3.5 Protective Enclosures

- 2.3.5.1 A protective enclosure (cover) shall be provided for the phase shifters.
- 2.3.5.2 Weather-resistant, electrically non-interfering plastic tape (tedlar-mylar or equivalent) shall cover the antenna radiating slots and prevent entrance and accumulation of water, sand and dust in the microwave elements.
- 2.3.5.3 The contractor shall supply a waterproof, soft plastic or coated or impregnated cloth hood to protect the antenna while not operated or while in storage.
- 2.3.6 Protective Finishes

The exterior surfaces of the antenna system (waveguides, mounting structure, enclosures, transceiver) shall be covered with protective coating. The color shall be silver or white, to minimize the heating due to solar radiation. The interior surfaces shall have appropriate corrosion-resistant finish.

2.3.7 Material Compatibility

Different materials in contact with each other shall be chosen with careful regard to the electrochemical series so that they are compatible and will not corrode because of electrical potential differences.

2.4 Testing

The contractor shall perform the following tests:

- 2.4.1 Laboratory tests for microwave components (vertical feed, horizontal array elements, etc).
- 2.4.2 Laboratory and range tests for the 9-element test array.
- 2.5 Calibration

All instrumentation used for laboratory and range testing shall be properly calibrated with standards traceable to the National Bureau of Standards.

2.6 Maintenance

For ease of maintenance, electrical and microwave components shall be mounted so as to permit field testing and replacement by qualified personnel.

- 2.7 Mobility/Transportability
- 2.7.1 In the next phase (C), the antenna system will be mounted on a servo pedestal located on an antenna vehicle. The vehicle will be transported by public highways and/or railroads between proving grounds. Within the proving grounds, graded, light duty, hard surface roads will be used. However, the system shall be capable of being moved at low speeds (5 mph) on unimproved dirt roads. The antenna system shall be able to withstand, without damage, the above transportation requirements.
- 2.7.2 During transportation within the proving grounds the overall system height shall be less than 16 feet, 12 feet desired. If it is necessary to lower the antenna to meet this requirement, the lowering mechanism shall be self-contained and hydraulically or hand operated. The width of the system during transportation shall not exceed 8 feet. When moving from site to site within the proving grounds, a maximum set-up time of 8 hours is required, four hours desired.
- 2.7.3 For transportation between proving grounds, it shall be possible to deploy the system into a configuration transportable over public roads and compatible with applicable federal, state and local regulations. If necessary, subsystem may be removed or lowered from the main assembly with the aid of a crane (to be provided by Proving Grounds).
- 2.8 Environmental Requirements
- 2.8.1 Temperature

The antenna system shall be capable of operating in an ambient air temperature range of -65°F to +165°F and maintaining the accuracy requirements specified in section 2 for an ambient air temperature range of -20°F to +120°F.

2.8.2 Wind

The antenna system shall be capable of operating and maintaining the accuracy requirements specified in section 2 in winds up to 30 mph. In addition, when the antenna is secured and not operating, it shall be capable of withstanding winds up to 75 mph.

2.8.3 Precipitation (Rain, Snow, Hail, Ice)

The antenna system shall be properly designed and fabricated to prevent limitation in accuracy and operational capability caused by internal leakage and accumulation of precipitation. The effects of external accumulation should be kept as low as possible by proper design.

2.8.4 Humidity

The antenna system shall be properly designed and fabricated to prevent deterioration of system performance due to humidity encountered in the continental United States.

2.8.5 Sand and Dust

The antenna system shall be properly designed and fabricated to prevent sand and dust particles from entering the interior of the system, accumulating there and causing electrical and/or mechanical interference.

2.8.6 Solar Radiation

The antenna system shall be designed to operate under extreme environmental conditions with a solar load of 360 BTU per square foot per hour taken at the worst orientation of the sun relative to the equipment. To limit the heating effect, the antenna system shall have an exterior reflective color of silver or white.

2.8.7 Shock

The antenna system, when properly mounted on servo pedestal and antenna vehicle, shall be able to withstand the effects of a 10g shock environment (any direction) during transit by truck. The equipment shall be designed to withstand humping loads common to rail transportation.

2.9 Reliability

0

0

The reliability of the antenna system shall be sufficiently high to permit achievement of the desired objective:

MTBF for the entire radar system - 200 hours.

2. DESIGN DESCRIPTIONS

The following sub-sections provide brief descriptions of the major components in the ARBAT antenna design. Detailed physical descriptions are generally not included in this section, except that in some instances basic dimensions are included on sketches to provide the reader with sufficient information to facilitate visualization of the component described.

Test results for critical parameters are included for those components where such tests are applicable.

Drawings for the antenna are packaged separately from this report (3 copies supplied to Picatinny Arsenal and requests for copies should be made there).

The following drawings are available at Picatinny Arsenal.

	Drawing	Component/Assembly
1.	140300-1	Antenna Assy, ARBAT
2.	140301-1	Back Structure, Antenna
3.	140311-1	Twist, 90°, W/G
4.	140309-2	Array Assy, W/G
5.	140309-2	Parts List
6.	140312-1	Flange
7.	140312-2	Flange
8.	140307-1	Feed Line
9.	140313-1	Load Assy
10.	140310-1	Comb
11.	140310-2	Comb
12.	140317-1	Comb
13.	140317-2	Comb
14.	140315-1	Structure
15.	140328-1	Bracket
16.	140328-2	Bracket

	Drawing	Component/Assembly
17.	140316-1	Panel
18.	140318-1	Bracket
19.	140319-1	Block
20.	140320-1	Retainer
21.	140308-1	Monitor
22.	140325-1	Load
23.	140321-1	Cover
24.	140322-1	Cover
25.	140323-1	Cover
26.	140324-1	Angle
27.	140302-1	Support
28.	140303-1	Support
29.	140304-1	Support
30.	140304-2	Support
31.	140305-1	Base
32.	140306-1	Clevis
33.	140326-1	Rod End
34.	140327-1	Clevis

2.1 Back Structure

0

The antenna back structure is a rigid welded aluminum (6061-T6) structure designed to support the microwave elements of the antenna with the associated phase shifter drive electronics and the transmitter/receiver. The structure is designed for mounting on a rotating pedestal which will provide the mechanical portion of the required beam scanning capability. A non-scalar structural schematic sketch is used for clarity in Figure 7 to illustrate the basic construction of the back support.

A full view, artists sketch, of the backside of the antenna with the transmitter/receiver mounted shows the position of the transceiver/mounting, Figure 8.

The measured weight of the completed back structure is 722.0 pounds which includes the array positioning combs.

The obvious prime requirement for the back structure is rigidity and desirably the rigidity should be achieved with reasonably light-weight. Computer defelection analysis results are shown in Figure 9.

The mechanical structure analysis for the total antenna structure is contained in Appendix A.




Figure 7. Back Structure Truss Elements






Figure 8. Back Structure/Transceiver Mounting

PREPARED	3. ELE	3/25/23	ITT Gilfillan Inc.	SHEET 13 OF
CHECKED			COMPUTER MODEL FOR	SKETCH NO.
APPROVED			STRUPAK AWALYSIS	THAT A






ASSUME CENTER SECTION TORQUE BOX TO

BE RIGHT & DEFLECTIONS ARE DUE TO BENDING

OF TRUSS STRUCTURE ONLY



0

Figure 9. Computer Deflection Analysis

2.2 Horizontal Array Waveguide Sections

The radiating elements in the ARBAT antenna are horizontal array waveguide sections. Radiation is via dual pairs of slots milled in the narrow dimension side. Array waveguide sections are fabricated from thin wall precision waveguide made from 6061-T6 aluminum alloy conforming to MIL-W-85/6 requirements. This waveguide is 0.400 by 0.750 inches inside and 0.476 by 0.826 inches outside. Each array section is 145.86 inches in length and contain 161 dual slot pairs (322 milled slots) in the narrow dimension radiating edge. Each individual array section is fitted with a flange at each end for mating with a diode phase shifter at the feed end and with a coupler flange plate at the opposite or performance monitor end. The flanges are welded at each corner to the mating waveguide and the remaining area of contact is then sealed.

Before assembly of the horizontal array sections, the slotted side is covered with a multi-layer RF transparent tape (G. T. Schjeldahl Co., Type G. 133500-014) and all surfaces are eventually painted with white epoxy paint.

Horizontal Array Section Test Data. - The following data represents the individual element test results obtained for finalized configurations. Consequently, the results presented represent the established requirements for which the production samples were later tested. This data is generally presented in one of two forms, tabular or graphic and in all instances the data is self explanatory. The following specific data is contained in this section:

- a. Insertion Phase Measurement/Comparison Test Set up (Figure 10)
- b. Insertion Phase Plot (after etching process) (Figure 11)
- c. Phase Error Plot (2nd aperture excitation at 9.3 GHz) (Figure 12)
- d. Phase Error Plot (2nd aperture excitation at 9.65 GHz) (Figure 13)
- e. Phase Error Plot (2nd aperture excitation at 10 GHz) (Figure 14)

- f. Amplitude Plot (1st aperture excitation at 9.65 GHz) (Figure 15)
- g. Amplitude Plot (2nd aperture excitation at 9.3 GHz) (Figure 16)
- h. Amplitude Plot (3rd aperture excitation at 10 GHz) (Figure 17)





Figure 10. Insertion Phase Measurement/Comparison Test Setup






Figure 11. Insertion Phase Plot (After Etching Process)

27/28




Figure 12. Phase Error Plot (2nd Aperture Excitation at 9.3 GHz)




Figure 13. Phase Error Plot (2nd Aperture Excitation at 9.65 GHz)




Figure 14. Phase Error Plot (3rd Aperture Excitation at 10 GHz)




Figure 15. Amplitude Plot (1st Aperture Excitation at 9,65 GHz)




Figure 16. Amplitude Plot (2nd Aperture Excitation at 9.3 GHz)

霊




Figure 17. Amplitude Plot 3rd Aperture Excitation at 10 GHz)

2.3 Vertical Feed Line

0

The vertical feed line provides the single RF connection between the transmitter/receiver and the antenna. The RF input/output connection is at the lower end of the vertical feed waveguide section. Connection to the feed line is made with a short section of flexible waveguide. The vertical feed distributes the input to individual horizontal arrays by way of four-port coupling apertures into 90 degree twist sections that distribute energy to and from the 167 horizontal array sections via the diode phase shifters. The 90 degree twist sections are attached to the vertical feed line by dip brazing. The feed line and its position in the antenna assembly are shown in the photograph, Figure 18.

Vertical Feed Line Configuration. - The feed line is 120.52 inches long and is fabricated in three separate sections from precision waveguide (aluminum) per MIL-W-85/1. Waveguide dimensions are 0.400×0.900 inside by 0.500×1.00 inch outisde. See drawing 140307 for design details (available at Picatinny Arsenal).

Vertical Feed Tests. - After finalization of design detail, tests to determine actual insertion loss and VSWR were run. The results of the tests are shown graphically in Figure 19 Insertion Loss, Figure 20 VSWR (Elements 113 to 167), and Figure 21 VSWR (Expanded Figure 20).




Figure 18. Vertical Line Feed in Assembled Antenna




Figure 19. Vertical Line Feed Insertion Loss vs Frequency




Figure 20. VSWR vs Frequency: Line Feed Section #3




Figure 21. VSWR vs Frequency: Line Feed Section #3 (Expanded Scale)

2.4 90 Degree Twist Crossguide Coupler Section

Horizontal array sections are coupled to the vertical feed line (via diode phase shifters) by a 90° twist waveguide section with four port coupling apertures. A loading block is inserted in the closed end of each coupler section opposite the feed line. Four port coupling slots match apertures in the vertical feed line. Attachment of coupling sections to the feed line is by dip brazing. The physical configuration of the production section is shown in the photograph, Figure 22.

Physical Configuration. - The crosscouplers are fabricated from precision waveguide (6061-F aluminum alloy in accordance with MIL-W-85/1). Figure 23 illustrates the configuration of the part. (See drawing 140311 for dimensions, available at Picatinny Arsenal.)

Coupler Testing. - Testing this element was relatively simple because of its configuration and previous tests for terminating loads and coupling slot dimensions. VSWR tests were conducted on a sample quantity of coupling sections with results shown in Figure 24.




Figure 22. Ninety Degree Twist Crossguide Coupler in Assembled Antenna

O




Figure 23. Ninety Degree Twist Crossguide Section




Figure 24. Ninety Degree Twist Section VSWR Plot

2.4.1 Load: Termination (Vertical Feed Coupler). - Equalizing termination loads are required for each coupler section at the vertical feed line. The loads used in the ARBAT antenna are fabricated from ECCOSORB 17 Compound, which is molded and then machined to final dimensions. The load element is then cemented to a waveguide cap plug and the assembly is installed in the ends of each coupling section. The load element is drilled for a 4-40 screw which further secures the load/plug assembly in the coupling section. All load elements in the 167 couplers are of uniform dimensions.

<u>Load Test.</u> - Sample loads were tested over the operating frequency range to insure acceptable return loss values. The VSWR values obtained from the finalized design are shown in Figure 25. For detailed design including dimensions see Drawing 140313 (available at Picatinny Arsenal).




Figure 25. Load: Vertical Feed Coupler VSWR Plot

2.4.2 Phase Randomization Blocks. - Phase randomization blocks are used in the beam scanning path to reduce the degree of phase quantization effect which may occur with digital phase shifters producing relatively large phase shift increments.

The method of overcoming the possible occurrence of phase quantization effects in the ARBAT antenna is through the installation of a dielectric material block in each 90 degree twist section. The blocks are fabricated from Rexolite material in a single width ($\frac{390}{400}$ inch) and six lengths (0.216; 0.207; 0.170; 0.709; 0.722; and 0.769 inch). The phase randomization blocks are installed in the narrow dimensions of each twist section at the end adjacent to the phase shifter. Each block is held in place by a single screw and epoxy adhesive. The position of the block in the 90 degree twist section is shown in Figure 26. The configuration and dimensions for the series of blocks is shown in Figure 27.

Phase Randomization Block Tests. - The parameters of significance in the phase randomization block design are insertion phase over the radar bandwidth and return loss over the operating frequency range. The results of tests using samples of each block configuration are shown in Figure 28, Phase Randomization Block Insertion — ase vs Frequency and Figure 29, Phase Randomization Block Return Loss vs Frequency

D




Figure 26. Phase Randomization Block Location in Coupler

O




Figure 27. Phase Randomization Block Series




Figure 28. Phase Randomization Block




Figure 29. Phase Randomization Block

2.5 Diode Phase Shifter

The ARBAT antenna uses digitally controlled diode phase shifters to phase the energy radiated by the horizontal array elements in accordance with computer/software controlled logic. Phase shifter control in the ARBAT antenna permits control of the pencil beam over the range of ±35 degrees in elevation with respect to beam normal. The ARBAT antenna requires 167 phase shifters which have been supplied as Government Furnished Equipment.

The reciprocal phase shifters provide four-bit phase control over the range of 9300 to 10,000 MHz. A total of 16 phase states may be set by the logic control resulting in a phase state range of 0 to 337.5 degrees in 22.5 degree increments.


The phase shifter unit package includes a driver circuit and space for a logic decoding package. The input to each phase shifter package comes from a beam steering buffer unit. The control logic for the array (167 phase shifters) functions in a serial mode and, the decoding process is similar to signal progression through a long shift register. Each phase shifter contains two four-bit shift registers as shown in the block diagram of Figure 30. The four-bit command is clocked into the first register of phase shifter number 1 on the first shift command. A load signal transfers the four-bit command to the second register whose outputs drive the phase shifter assembly. A second shift command transfers the four-bit command to the first register of the second phase shifter where it is loaded by a load command.

The sequence described above is repeated from phase shifter to phase shifter with each decode logic assembly receiving data from the previous one (along with the bussed control commands). The output of the 167th logic assembly is fed back to the beam steering buffer for integrity verification.

The sampled output of each driver is then amplified and sent to builtin test equipment and compared to the phase-set command. A determination is made as to whether the phase shifter is receiving the correct command, and incorrect command, or if commands are reaching the unit.

The output voltages of the driver power supplies are also monitored. The outputs are compared with a predetermined reference voltage from a voltage regulator. If the output voltages vary by more than ±5 percent, an

"abnormal" condition is indicated. Phase shifter logic control organization is illustrated in Figure 30. Phase shifter position in relationship to the 90 degree twist waveguide section is shown in the assembled antenna in the photograph, Figure 31.



1

Figure 30. Phase Shifter Decode Logic Organization



Figure 31. Phase Shifter Position in Assembled Antenna

2.6 ARBAT Antenna Performance Monitor Concept

The purpose of the performance monitoring features incorporated into the ARBAT antenna design is to provide a dynamic checking capability on the operability and performance of the overall antenna subsystem. In addition to the latter basic function, the monitor capability facilitates the location of defective components or components operating in a degraded mode.


The performance monitoring function in the ARBAT antenna is accomplished by the inclusion of the performance monitor line and monitor line couplers described in the following section (2.6.1). The additional components required to monitor the signal detected at the output of the vertical monitor line are not parts of the antenna and are not described in this report.

In operation, overall general antenna performance may be ascertained by observing the pattern presentation on a monitor display. If the observed display is abnormal indicating degraded performance, a special diagnostic routine generated by the CPU may be initiated which supplies logic commands to the phase shifter control circuitry. By means of these diagnostic commands, the cause of the abnormal display may be localized to the individual horizontal array element and/or phase shifter in the individual array section that is responsible for the indication.


The sketches in Figure 32 (Performance Monitoring Concept) illustrate the fault detection process.

Point A of the antenna fault detection approach schematic is the location of a single ended mixer. At this point, a signal from a good antenna would be similar to the second illustration when the phase shifters are programmed through a standard scan. If the antenna has component failures affecting the elevation pattern, overall system performance will be degraded, and the sidelobe pattern will be distorted as in the third figure.


To localize the particular waveguide/phase shifter element, each phase shifter may be separately cycled linearly in phase. In a good system the amplitude waveform at point A will go through a negative zero crossing as the phase is cycled through the 90 degree phase shifter point.



Fault Detection Approach Schematic



Monitored Signal for Antenna without Failures



Monitored Signal for Antenna with Failures

Figure 32. Performance Monitoring Concept

A circuit coupled to point A, consisting of a gate seeking coincidence between a pulse generated at the negative zero crossing and another generated at the 90 degree phase instant, will provide an output if the element conditions are normal.

2.6.1 Performance Monitor Line. - The performance monitor line is connected between the last dual slot pair and the terminating load in each horizontal array section. The purpose of the performance monitor line is to collect the residual RF energy that is not radiated in each horizontal array. The residual energy is combined in the line and is detected by a diode detector connected to the lower end of the line by a coaxial line which is not a part of the antenna proper. The detected signal resulting from the combination of residual energy contributed from all elements is used to provide a dynamic check on antenna performance/status during operation.

The performance monitor line is fabricated in three separate sections using precision waveguide (0.400 x 0.900 inch inside dimension by 0.500 x 1.000 outside dimension) for the vertical feed line and smaller precision waveguide (0.400 x 0.750 inch inside by 0.476 x 0.826 inch outside dimension) for the horizontal coupling sections. The couplers, as will be noted are fabricated from the same material (type and size) as the horizontal array elements.

The coupling sections contain a milled nondirectional four port slot which couples the short horizontal sections to the vertical monitor line. Each coupling section is terminated with a matched loading block. The coupling coefficients of the sections are adjusted carefully to match the Taylor excitation generated by the vertical feed line. The coupling value is a function of slot length. The coupling values are maintained low in view of the low energy level required for the performance monitoring function.

The slot dimensions used for the 167 coupler sections in the ARBAT antenna are contained in Figure 33. Slot coupling values in voltage amplitude, coupling power ratio and coupling in dB on which the slot configurations were based are listed in Figure 34.

The performance monitor line is shown in the assembled antenna in Figure 35 and a closeup view of a section of the line shows mounting details (Figure 36).

POWER INTO LOAD = 0.60000 (LENGTH UF SLOT IS GIVEN AS 1/2 LENGTH 0.15936 0.15943 0.15951 0.15958 0.15966 0.15973 0.15988 0.15634 0.16267 127 0.16636 0.16267 0.16275 0.16283 0.16292 88 0.16300 0.16307 44 86 128 40 0.16654 8 0.15648 0.16664 88 88 130 0.15662 47 29 131 0.16673 48 132 90 6789 91 0.15676 0.16317 0.16325 0.16334 6 0.16351 H 0.16359 89 0.163577 0.16692 3 92 93 94 95 50 0.15988 134 0.15683 0.15689 136 137 138 30 139 0.16004 53 54 55113 0.15703 11 0.16730 8 0.16019 96 0.15718 0.15725 0.15732 0.15739 0.15746 0.15753 13 0.16749 56 0.160357 98 70 99 0.16759 0.16385 15 0.16769 141 0.16050 58110 100 0.16778 0.16402 0.16411 0.16420 0.16428 0.16437 10167 143 144 24 145 17 59 0.16788 0.16066 102 60 0.15760 0.15767 0.15774 0.15781 0.15789 0.15796 0.16808 19 61 0.16081 8 146 20 104 0.16089 0.16097 0.16105 105 21 63 0.16827 0.16437 0.16446 0.16455 0.16464 0.16472 0 0.16481 22 23 24 64 106 148 20 0.16837 149 150 151 0.16847 0.16129 0.16137 0.16137 0.16145 0.16145 66 108 60 0.15803 0.15810 0.15817 25 0.16867 68 100 69 70 71 72 73 152 153 154 155 26 0.16877 111 C.16490 0.16887 0.16499 28 0.15825 0.16897 0.15832 0.161538 29 113 0.16908 0.16526 0.16535 0.165344 156 157 158 10 159 0.16918 31 0.15847 0.16169 115 0.16928 0.16936 % 74 116 0.15854 0.16171 0.16948 DE 33 0.15861 0.16193 0.16544 0.16553 0.16563 0.16571 0.16580 0.16589 0.16608 0.16617 34 76 77 91 0.15869 118 50 160 0.16201T 0.16209T 0.16217 0.16969 0.15876 119 161 0.15883 78 90 79 36 0.16979 121 163 0.16990 38 0.15898 80 0.16226 122 164 0.17000 0.15906 0.15913 0.15921 81 0.17011 82 83 84 0.16242 124 166 167 1 40 1.402 41 0.17032 0.15928 0.16259 126

SLOT WIDTH = 0.062 +.002 FREQUENCY= 9.650003HZ A DINENSION = 0.90000 B DIMENSION = 0.40000

0.90000 IN. 0.40000 IN.

9.65000 GHZ

0.90000IN 0.400001V

0.00255 DB

0.00000

FREDURKY = 9.55000 3M.

4.6. A DIMENSION= 0.90000IN

4.6. B DIMENSION= 0.40000I

ELEMENT SPACING= 0.72000IN

TE MODE(N.M) = 1.00000 0.

WAVEGUIDE LOSSES = 0.00255 0

FREQUENCY =

Figure 33. Performance Monitor Slot Dimensions

```
9.65000
 FRFU =
 SPACE = 0.72000
SERPENTINE SPACING
                              NG = 0.00000
= 0.60000
= 0.00000
 POWER INTO LOAD WAVEGUIDE LOSSES
                                 0.00000
  TOTAL
            AMPLITUDE C (PWR RATIO)
             (V)
0.04389
0.04389
                                0.00192 -27.14919
0.00193 -27.13825
0.00193 -27.12730
                                                                              0.04389
                                                                                                0.00224 -26.48931
0.00225 -26.47700
0.00225 -26.46466
                                                                              0.04389
                                                                                                                                    114
                                                                                                                                               0.04389
                                                                                                                                                                 0.00265 -25.75297
                                                                                                                                               0.04389
                                                                                                                                                                 0.00266 -25.73886
0.00267 -25.72471
                                0.00194 -27.11633
0.00194 -27.10533
0.00195 -27.09432
0.00195 -27.08328
0.00196 -27.07222
              0.04389
                                                                      60
                                                                               0.04389
                                                                                                0.00226 -26.45230
0.00226 -26.43991
0.00227 -26.42749
                                                                              0.04389
                                                                                                                                               0.04389
                                                                                                                                                                 0.00268 -25.71052
              0.04389
                                                                      62
                                                                      63
                                                                              0.04389
                                                                                                                                               0.04389
                                                                                                                                                                 0.00270 -25.68203
                                                                                                0.00228 -26.41504
0.00228 -26.40256
                                                                                                                                                0.04389
                                                                                                                                                                 0.00271 -25.66772
0.00272 -25.65338
                                0.00196 -27.06114
0.00197 -27.05004
0.00197 -27.05891
                                                                                                                                     121
                                                                                                                                               0.04389
                                                                      65
              0.04389
                                                                              0.04389
                                                                                                0.00229 -26.39006
                                                                              0.04389
                                                                                                                                                                 0.00272 -25.63900
0.00273 -25.62458
                                                                                                                                               0.04389
              0.04389
                                0.00198 -27.02776
                                                                              0.04389
                                                                                                 U.00230 -26.36496
              0.04389
                                                                     68
69
70
71
72
73
74
75
76
77
                                                                                                                                     124
                                                                                                                                               0.04389
                                                                                                                                                                 0.00274 -25.61011
                                                                                                0.00231 -26.35237
0.00232 -26.33975
0.00232 -26.32710
0.00233 -26.31442
                                                                                                                                    125
126
127
                                                                                                                                                                 0.00275
              0.04389
                                0.00199 -27.00540
              0.04389
                                                                               0.04389
                                                                                                                                               0.04389
                                                                                                                                                                               -25.58107
                                                                                                                                                                 0.00277 -25.56649
0.00278 -25.55187
                                                                              0.04389
                                                                                                                                               0.04389
                                0.00200 -26.98295
0.00200 -26.97169
0.00201 -26.96041
                                                                              0.04389
0.04389
0.04389
                                                                                                                                               0.04389
              0.04389
                                                                                                0.00234 -26.30171
0.00235 -26.28997
0.00235 -26.27620
0.00235 -26.27620
0.00236 -26.26340
0.00237 -26.25057
                                                                                                                                               0.04389
                                                                                                                                                                 0.00279 -25.53721
                                                                                                                                                                  0.00280 -25.52251
              0.04389
                                0.00201 -26.94911
0.00202 -26.93778
0.00202 -26.93778
0.00203 -26.92643
0.00203 -26.91506
0.00204 -26.90366
                                                                              0.04389
                                                                                                                                     131
                                                                                                                                               0.04389
                                                                                                                                                                 0.00281 -25.50776
                                                                                                                                                                 0.00282 -25.49297
                                                                              0.04389
                                                                                                                                               0.04389
              0.04389
                                                                                                0.00237 -26.23057

0.00237 -26.23771

0.00238 -26.22482

0.00239 -26.21189

0.00239 -26.19894

0.00240 -26.18596
                                                                              0.04389
                                                                      78
79
                                                                                                                                               0.04389
                                                                                                                                                                 0.00284 -25.46327
                                                                                                                                     135
                                                                                                                                                                  0.00285
                                                                                                                                                                               -25.44836
              0.04389
                                0.00204 -26.90366

0.00204 -26.809224

0.00205 -26.86080

0.00205 -26.86033

0.00206 -26.85784

0.00207 -26.83479

0.00207 -26.83323

0.00207 -26.83323
              0.04389
                                                                                                                                                                 0.00286 -25.43341
                                                                      80
                                                                              0.04389
                                                                                                                                     136
                                                                                                                                               0.04389
                                                                     82
83
84
                                                                              0.04389
0.04389
0.04389
                                                                                                                                     138
                                                                                                                                               0.04389
                                                                                                                                                                 0.00288
              0.04387
                                                                                                                                                                               -25.40337
                                                                                                0.00241 -26.17294
0.00242 -26.15990
0.00242 -26.14682
                                                                                                                                    139
                                                                                                                                               0.04389
                                                                                                                                                                 0.00269 -25.38828
0.00290 -25.37316
              0.04389
                                                                              0.04389
              0.04389
                                                                      85
                                                                                                                                     141
                                                                                                                                               0.04389
                                                                                                                                                                 0.00291 -25.35798
                                                                                                0.00247 -26.14682
0.00243 -26.13371
0.00244 -26.12057
0.00245 -26.10739
0.00245 -26.09419
                                                                     86
                                0.00208 -26.81164
0.00208 -26.80003
0.00209 -26.78840
                                                                                                                                               0.04389
                                                                                                                                                                 0.00293 -25.32751
              0.04389
                                                                              0.04389
                                                                                                                                    143
                                                                     88
                                                                              0.04389
                                                                                                                                    144
                                                                                                                                                                 0.00294
                                                                                                                                               0.04389
                                                                                                                                                                               -25.31220
                                                                                                                                                                               -25.29685
                                                                                                                                               0.04389
              0.04389
                                                                                                0.00245 -26.08095
0.00247 -26.06768
0.00248 -26.05437
                                0.00210 -26.77674
                                                                              0.04389
                                                                                                                                                                 0.00296 -25.28145
0.00297 -25.26601
                                                                      90
                                                                                                                                    146
                                                                                                                                               0.04389
                                0.00211 -26.75335

0.00211 -26.75335

0.00211 -26.74162

0.00212 -26.72986

0.00212 -26.71608

0.00213 -26.70627
                                                                                                                                                                 0.00298 -25.25053
              0.04389
                                                                      92
                                                                              0.04389
                                                                                                                                    148
                                                                                                                                               0.04389
                                                                      93
                                                                              0.04389
                                                                                                0.00248 -26.04103
0.00249 -26.02766
                                                                                                                                    149
                                                                                                                                                                 0.00299 -25.23499
0.00300 -25.21941
                                                                                                                                               0.04389
                                                                                                                                               0.04389
                                                                                                0.00250 -26.01426

0.00251 -26.00082

0.00251 -25.98735

0.00252 -25.97385

0.00253 -25.96030
              0.04384
                                                                      95
                                                                              0.04389
                                                                                                                                    151
                                                                                                                                               0.04389
                                                                                                                                                                 0.00301 -25.20378
                                                                                                                                    153
154
155
              0.04389
                                0.00214 -26.69444
0.00214 -26.68258
                                                                              0.04389
                                                                                                                                                                 0.00303 -25.17239
                                                                                                                                               0.04389
                                                                                                                                               0.04389
                                                                                                                                                                 0.00305 -25.15662
                                0.00215 -26.6707C

0.00215 -26.65879

0.00216 -26.64686

0.00217 -26.63490

0.00217 -26.62291
                                                                                                                                               0.04389
                                                                                                                                                                 0.00306 -25.14080
              0.04389
                                                                      99
                                                                              0.04389
                                                                                                0.00254 -25.94673
0.00255 -25.93312
              0.04389
                                                                              0.04389
                                                                                                                                    156
157
                                                                                                                                                                 0.00307 -25.12493
0.00308 -25.10902
                                                                                                                                               0.04389
                                                                                                0.00255 -25.91948
0.00256 -25.90580
0.00257 -25.69208
              0.04389
                                                                              0.04389
                                                                                                                                    158
                                                                                                                                               0.04389
                                                                                                                                                                 0.00309 -25.09305
                                                                                                                                               0.04389
              0.04389
                                0.00218 -26.61090
                                                                    104
                                                                              0.04389
                                                                                                                                    160
                                                                                                                                               0.04389
                                                                                                                                                                 0.00311 -25.06097
                                                                    105
                                                                                                0.00258 -25.87834
                                                                                                                                    161
                                                                                                                                               0.04389
                                                                                                                                                                 0.00312 -25.04486
              0.04389
                               0.00219 -26.58679
                                                                    106
                                                                                                0.00259 -25.86455 0.00259 -25.85073
                                                                                                                                                                 0.00314 -25.02869
0.00315 -25.01248
0.00316 -24.99621
                                                                              0.04389
                                                                                                                                    162
                                                                                                                                               0.04389
                                                                                                                                    163
                                                                                                                                               0.04389
                                                                                                0.00260 -25.63688
                               0.00220 -26.56259
0.00221 -26.55044
0.00221 -26.53827
              0.04389
                                                                                                                                               0.04389
                                                                    108
                                                                              0.04389
                                                                                                0.00261 -25.82299
0.00262 -25.80906
0.00263 -25.79509
                                                                                                                                                                 0.00317 -24.97989
0.00318 -24.96352
                                                                              0.04389
                                                                                                                                    165
                                                                                                                                               0.04389
                                                                    110
              0.04389
                               0.00222 -76.52607
                                                                              0.04389
                                                                                                                                    167
                                                                                                                                               0.04389
                                                                                                                                                                 0.00320 -24.94710
              0.04389
                                                                                                                                                    1 - 24
                                                                                                                                                    25 - 45
                                                                                                                                                                    0.394 (.393 - .395)
5005
                                                                                                                                                    46 - 67
                                                                                                                                                                     .390 (.389 TO .391)
                                                                                                                                                    68 to 91
                                                                                                                                                                     .386 (.385 - 387)
                                                                                                                                                    92 - 112
                                                                                                                                                                   382
```

-

ĕ

¢

4

8

3

3

1

Figure 34. Slot Coupling Values




Figure 35. Performance Monitor Line in Assembled Antenna




Figure 36. Performance Monitor Line (Close-Up View)

2.6.2 Loads: Performance Monitor Line. - Equalizing termination loads are required to terminate the horizontal array RF signal path, which in the ARBAT antenna is the extreme end of each coupling section attached to the performance monitor line. The performance monitor line loads are fabricated from material identical to that used for fabrication of the vertical line feed load elements, however the design and method of installation differs radically. These load elements are of uniform dimensions for all 167 elements. Oversize loads are molded from ECCOSORB 17 compound using an appropriate catalyst and milled to final dimensions. The load elements are chamfered at each edge of the surface contacting the wide dimension of the waveguide. In installation the load element is pressed into the waveguide together with a precut section of foam material the width of the load element and of a height to fully fill the space between the top of the element and the top inside wall of the waveguide above the load. The foam block holds the load firmly in place and epoxy adhesive is injected into the openings produced by the champfer at each corner of the waveguide.

For detailed design of the load element see Drawing 140325, Load, Monitor (available at Picatinny Arsenal).

Load Tests. - Tests to ascertain the return loss (VSWR) of the final load design were run throughout the antenna operating frequency range. Results of the tests are shown in Figure 37.




Figure 37. Load Block VSWR Measurement

3. TEST PROGRAM

Antenna Pattern Measurements

A major part of the ARBAT antenna development phase was the fabrication, testing, modification and retest of critical elements comprising the antenna subsystem. The procedure, which followed the paper design and computer analyses, was based on intermediate test results of single components followed by three* array range tests. On completion of these tests and after incorporation of changes determined necessary to optimize component design, a nine element test array was assembled using the optimized components. The nine element array configuration was selected as the minimum number of elements capable of producing patterns that reliably reflect the validity of the component designs, providing a confident prediction of the complete array performance.

3.1 Short Array (3 Section) Tests.

The 3 section array tests were made using a single excited horizontal array section between two "dummy" array sections positioned to provide a realistic environment for the active element. Short comb sections were used to maintain the relative positions of the three elements. The 3 section array was assembled and tested in the Van Nuys plant RF test chanber for insertion loss, VSWR (return loss) and phase error. The results of these tests are contained in the following figures. The last illustration is a computed pattern prediction based on the 3 element array phase and amplitude excitation measurements.

Figure 38. Horizontal Array Element Insertion Loss

Figure 39. Horizontal Array Element Return Loss

Figure 40. Horizontal Array Element Return Loss (Expanded D2 RL)

Figure 41. Predicted Pattern (3 Element Test)

^{*}One Excited Array and Two Dummy Arrays




Figure 38. Horizontal Array Element Insertion Loss (Dual Slot Radiators)





Figure 39. Horizontal Array Element Return Loss (Dual Slot Radiators)



D-2 Horizontal Array Element Return Loss (Expanded D2 RL) Figure 40.




Figure 41. Predicted Pattern (3 Element Test)

3.2 Nine-Element Test Array

The nine-element range tests were designed to determine the validity of all previous tests and modifications resulting from intermediate single element testing and the three element tests in the preceding section. For the purpose of these tests it was necessary to introduce phase changes in each horizontal array input by means of small waveguide sections containing Rexolite phase shift blocks in lieu of the diode phase shifters which were not available. The phase shifting elements fabricated for these tests duplicate the electrical function of the phase shifters and insure that the results obtained are transferable to the same array if excited via the phase shifters which will be used in the operational system. Mechanically, the Rexolite block phase shift devices differed significantly from the actual diode phase shifter, as will be noted in the test array sketch, Figure 43, largely in that an "in-line" configuration was used in the test device assembly, whereas the diode phase shifters contain a 90 degree bend at the point at which the connection to the horizontal array is made. A quarter wave transformer was inserted between the phase shift test device and the horizontal array elements.

Horizontal array elements for the nine-element test array included one array element fabricated during the earlier tests in which a single array was tested singly and mounted between two 'dummy' elements to form a three-array assembly. In order to provide a realistic electrical environment for the nine-element array, a 'dummy' horizontal element was positioned on the outside of the first and last excited elements in the test assembly.

A short vertical feed line was fabricated for use with the test array assembly. The nine-element test array pictorial schematic is shown in Figure 42. The test array is shown mounted on a test fixture during range tests in Figure 43.

After alignment of the test array with the transmitting antenna, tests were conducted to determine elevation scan angles versus phase shift increments and azimuth patterns at beam normal, mid scan, and at scan limits. All tests were repeated at 9.3, 9.65 and 10.0 GHz.

0

0

3.2.1 Test Patterns

Figure 44. Nine-Element Test Array Elevation Scan Figure 45. ARBAT 9-Element Test Array Pattern Figure 46. ARBAT 9-Element Test Array Pattern Figure 47. ARBAT 9-Element Test Array Pattern Figure 48. ARBAT 9-Element Test Array Pattern Figure 49. ARBAT 9-Element Test Array Pattern Figure 50. ARBAT 9-Element Test Array Pattern Figure 51. ARBAT 9-Element Test Array Pattern Figure 52. ARBAT 9-Element Test Array Pattern Figure 53. ARBAT 9-Element Test Array Pattern Figure 54. ARBAT 9-Element Test Array Pattern Figure 54. ARBAT 9-Element Test Array Pattern




Figure 42. Nine-Element Test Array Assembly




Figure 43. Nine-Element Test Array Assembled

ITEM	SCAN ANGLE ELEVATION (DEG)	FREQ GHZ	Ø BLOCKS	
1	0.0	9.3	1. 0.0 2. 45 3. 67.5 4. 112.5 5. 135	6. 180 7. 225 8. 247.5 9. 292.5
2	0.0	9.65	1. 0 2. 22.5 3. 45 4. 67.5 5. 90	6. 135 7. 157.5 8. 180 9. 202.5
3	0.0	10.0	1. 0.0 2. 22.5 3. 22.5 4. 45 5. 67.5	6. 67.5 7. 90 8. 112.5 9. 112.5
4	-17.5	9.3	1. 0 2. 337.5 3. 315 4. 292.5 5. 247.5	6. 225 7. 202.5 8. 180 9. 157.5
5	-17.5	9.65	1. 0.0 2. 315 3. 292.5 4. 247.5 5. 202.5	6. 157.5 7. 135 8. 90 9. 45
6	-17.5	10.0	1. 0 2. 315 3. 270 4. 202.5 5. 157.5	6. 112.5 7. 45 8. 0 9. 315
7	-35	9.3	1. 0 2. 270 3. 202.5 4. 112.5 5. 45	6. 315 7. 225 8. 157.5 9. 67.5
8	-35	9.65	1. 0 2. 270 3. 157.5 4. 67.5 5. 337.5	5. 247.5 7. 135 8. 45 9. 315
9	-35	10.0	1. 0 2. 247.5 3. 135 4. 22.5 5. 270	6. 157.5 7. 45 8. 292.5 9. 180

Figure 44. Nine-Element Test Array Elevation Scan




Figure 45. ARBAT 9-Element Test Array Pattern (Beam Normal) (9.30 GHz)





Figure 46. ARBAT 9-Element Test Array Pattern (Beam Normal) (9,65 GHz)

¢




ARBAT 9-Element Test Array Pattern (Beam Normal) (10.0 GHz) Figure 47.

-


3

2




ARBAT 9-Element Test Array Pattern (Mid-Scan) (9.3 GHz) Figure 48.


e



ARBAT 9-Element Test Array Pattern (Mid-Scan) (9.65 GHz) Figure 49.



ARBAT 9-Element Test Array Pattern (Mid-Scan) (10.0 GHz) Figure 50.



ARBAT 9-Element Test Array Pattern (Scan Limit) (9.3 GHz) Figure 51.





Figure 52. ARBAT 9-Element Test Array Pattern (Scan Limit) (9.65 GHz)



ARBAT 9-Element Test Array Pattern (Scan Limit) (10, 0 GHz) Figure 53.




Figure 54. ARBAT 9-Element Test Array Pattern (Center Element Broadside) (9.65 GHz)

4. SUMMARY OF TEST RESULTS

Test results throughout the ARBAT antenna development program have been consistent with the design goals and with the performance of both component parts tested individually and as partial arrays.

Scan coverage and radiation patterns demonstrated in the nineelement test array range testing program were in accordance with the design requirement and predicted performance.

Based on extensive experience in the development of similar antenna subsystems, the results from the 9-element tests can be assumed to be reliably indicative of the full (167 element) array performance with the operational phase shifters.

APPENDIX A
STRUCTURES ANALYSIS

PREPARED	APD	1/30/73	ITT Gilfillan Inc.	SHEET	Of
			THE PROJECTILE TEACKING	SKE	TCH NO.
CHECKED			RADAR		
APPROVED			STRUCTURES ANALYSIS		

TRAILER MOUNTED AUTENNA

DESEN PARAMETERS

- 1. ERROR (a) TOTAL BUDGET ERROR (Et) = 2.0 MILLI IZADIAN
 - (b) ASSUMED MECHANICAL TO DATA TAKE-OFF = 25% OF TOTAL

(Em) = 0.50 MR


(C) TRAILER & JACK SYSTEM ERROR

Z. TEMPERATURE

0

WIND LOADS

(b) The thy = 20 f's max (RAILROAD HUMPING IMPACT)



NORMAL TRANSPORT COORDINATE SYSTEM


X" AXIS - FORE & AFT

- CURBSIDE & POADSIDE

PREPARED	480	1/30/73	ITT Gilfillan Inc.	SHEET Z OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

5 AZIMUTH TRACKING - REQUIREMENTS

ANGULAR VELOCITY & ACCELERATION ANALYSIS



CONSIDER PROJECTILE AT ANY TIME "L"


BY DEFINITION Ro = Rocos 45°

$$\frac{de}{dt} = \frac{V_{pt}}{R_{o}}$$

$$\frac{de}{dt} = \frac{V_{p}/R_{o}}{1 + (\frac{V_{pt}}{R_{o}})^{2}}$$

$$\frac{d^{2}e}{dt} = \frac{-z(\frac{V_{p}}{R_{o}})^{2}t}{[1 + (\frac{V_{p}t}{R_{o}})^{2}]^{2}}$$

$$\frac{d^{2}e}{dt} = \frac{-z(\frac{V_{p}}{R_{o}})^{2}t}{[1 + (\frac{V_{p}t}{R_{o}})^{2}]^{2}}$$



PREPARED	APO	1/30/73	ITT Gilfillan Inc.	SHEET 3 OF
- ALPANED			THE PEOLECTILE TRACKING	SKETCH NO.
CHECKED			SACAS	
			STOUCTURES ANALYSIS	

AZIMUTH TRACKING

ANGULAZ VELOCITY & NODEL ERATION (CONT'D)

SOLVE FOR INITIAL STARTING TIME LI @ 0=45°

:.
$$t_{au45}^{\circ} = 1.0 = \frac{V_{pti}}{R_{o}}$$

 $t_{i} = \frac{R_{o}}{V_{p}} = \frac{R_{p} \cos 45^{\circ}}{V_{p}}$
 $t_{i} = \frac{1500 \times 707}{1000}$
 $t_{i} = 1.06 \text{ Sec.}$

PER P 2.1 REQUIREMENTS

WITH ELECTRONIC STAN @ ± 3.5°/SEC.

SOLVE FOR MINIMUM RP TO SATISFY BOTH CONDITION

SOWE EDW 3 FOR RD FOR 0 - 0.70 RAD/SECT-

FORM 118 - (5-67)

PRIPARED	APO	1 30 73	ITT Gilfillan Inc.	SHEET 4 OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

MIENNA SYSTEM

INTRODUCTION: THE ANTENNA SYSTEM WILL BE MOUNTED ON A VEHICLE BED WITH JACK PAD PROVISIONS TO LIFT THE ENTIRE OR PORTION OF THE SPRUNG MASS OF THE VEHICLE-ANTENNA SYSTEM. THE ANTENNA WILL BE OF NERRY WITH PHASE SHIFTER TYPE DESIGN ATTACHED TO A CENTER MAIN STRONG BACK STRUCTURE WHICH SERVES AS A TORQUE TUBE AS WELL AS A CANTILEVER BORN FOR ELEVATION BENDING MOMENT, THE PUTENIA WILL HAVE A MAXIMUM THE TRANSCEIVER ASSEMBLY WILL BE MOUNTED TO THE MAIN BACK STRUCTURE SO POSITIONED FOR MINIMUM MASS MUMENT OF INERTA EFFECT ABOUT THE AZIMUTHAL ANS.

THE ANTENNA SYSTEM WILL BE ASSEMBLED TO A PEDESTAL WHICH HOUSES THE BULL GEAR - BEARING ASSEMBLY, DRIVE MOTOR, GEAR BOY & DATA TAKE-OFF, EXISTING AN SPS-48 PEDESTAL CAN BASILY BE ADAPTED IN THIS DESIGN, THE PEDOSTAL IN TURN IS PERMANENTLY BOLTED TO THE TRAILER BED. THE TRAILER IN THE JACKED POBITION SHALL BE SO DESIGNED TO ACT AS NEARLY RIGID FOR SUDDENLY APPLIED TORSIONAL LOAD AT THE PEDESTAL BASE, THE JACK-PADS WILL REST ON A PREPARED ON SITE GROUND FOOTING. THE 8 HOURS SET UP TIME CAN BE ACHIEVED. THE JACK ASSEMBLY LATERAL DEPLETION (WHICH INCLUDES ANY ATTACHMENT TO THE TRAILER DODY) SHALL BE HELD TO AN ACCEPTABLE LIMIT UNDER OPERATING CONDITION.


EPARED	APO	1/30/73	ITT Gilfi	lan Inc.	SHEET	5 %
MECKED			PROJECTILE RADAR	TEACKING	THE RESERVE AND ADDRESS OF THE PERSON NAMED IN	ETCH NO.
PROVED			STRUCTURES	ANALYSIE		
An.	LENNY SA	STEM W	EIGHTS			
WE	THE THE	ALYSIS	- X BOND RA	DAR		
Co	MPONENT	S				
(1) (Z) (3) (4)	W.G. FLAN	685 (167) HIFTERS (2004 FT @ .12*/1 # HARDWARES 167 @ .9# BA) + BENT TRANSITI		=	240 L8 30 L8 150 L8 25 L8
(5)	BUFFER	BEAM,				25 48
(6)		SUPPLY	DOM:			50 LB
(7) (8)	TRANSCE	BUS BAR,	DOHYDRATOR, BC			30 LB
400					-	
(9)	COOLIN	IG FANS			=	15 LR
(9)	COOLIN	ig fans		UR-TOTAL		15 LB
(9)	COOLIN	ig fans	=	UB-TOTAL(1)		940 LB
				UB-TOTAL(1)		
STRU	octures &	Housing	S			
STRU	UCTURES &	HOUSING	S_ DESTAL (ROTATING	MASS ONLY)	E	940 4
5TRC	UCTURES &	HOUSING	S	MASS ONLY) = 24010) +CLE	vises =	940 LB
5TRC	UCTURES &	HOUSING	S DESTAL (ROTATING ER (D=46,012),D; A=50112 Dav=37.0	MASS ONLY) = 24010) +CLE	Vises =	940 LB
(1) (C) (C)	UCTURES & USING AN/9 D) TOP PLA D) INNER BE	HOUSING 595-48 FE TE ADAPT 35 RACE	S DESTAL (ROTATING ER (D=46.01), Di A=50112 Day=37.0	MASS ONLY) = 24010) +CLE	Vises =	940 LB 170 LB 170 LB
5TRC (1) (0) (0) (2)	UCTURES & USING AN/S D) TOP PLA D) INNER BE	HOUSING FRE ADAPT RACE FRER HOUS	S DESTAL (ROTATING ER (D=46,012),D; A=50112 Dav=37.0	MASS ONLY) = 24010) +CLE	Vises =	940 LB 170 LB 170 LB 290 LB
(1) (C) (C) (C) (C) (C) (C) (C) (C) (C) (C	UCTURES & USING AN/S D) TOP PLA D) INNER BO PHASE SHI COMPONENT CENTER M	HOUSING FRE ADAPT GENERALE FRER HOUSINEUS (S) (S)	S DESTAL (ROTATING DER (D=46.01), Di A=501N ² Dav=37.0 SU UG+TRAUSITION P OE-BOX BEAM TUBE	MASS ONLY) = 24011) + CLE 111) B-TOTAL(2) LATE	VISES = = = = = = = =	940 LB 170 LB 170 LB 290 LB 290 LB
(1) (C) (C) (C) (C) (C) (C) (C) (C) (C) (C	UCTURES & USIUG DU/S D) TOP PLA D) INNER BO PHASE SHI COMPONENT CENTER M	HOUSING FRE ADAPT FRER HOUSITEWS (\$) (\$ AUU TOROUTO	S DESTAL (ROTATING DER (D=46.01), Di A=501N ² Dav=37.0 SU UG+TRAUSITION P OE-BOX BEAM TUBE	MASS ONLY) = 24011) + CLE 111) B-TOTAL(2) LATE	VISES = = = = = = = =	290 LB 290 LB 290 LB 20 LB
(1) (C) (C) (C) (C) (C) (C) (C) (C) (C) (C	UCTURES & USIUG DU/S D) TOP PLA D) INNER BO PHASE SHI COMPONENT CENTER M	HOUSING FRE ADAPT FRE HOUSITEUS (5) (6) AND TORON 10.29 , 24	S DESTAL (ROTATING ER (D=46.01), Di A=50112 Dav=37.0 SU UG+TRANSITION P O & HOUSING DE-BOX BEAM TUBB O x 32.0 75 FT @1.31 #/FT	MASS ONLY) = 24011) + CLE 111) B-TOTAL(2) LATE	VISES = = = = = = = = = = = = = = = = = =	940 LB 170 LB 170 LB 290 LB


FORM 118 - (5-67)

TOTAL WEIGHT

= 2070 LBS


	APO .	1/30/73	ITT Gilfillan Inc.	SHEET (OF
PREPARED			THE PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	





PREPARED	SPD	1/30/73	ITT Gilfillan Inc.	SHEET	Of
CHECKED			PROJECTILE TRACKING	SKET	CH NO.
APPROVED			STRUCTURES DUALYSIS		

MASS DISTRIBUTION ANALYSIS (CONTO)



PLAN VIEW - MASS DISTRIBUTION

$$\overline{Z} = \frac{Z45 \times 22.0 + 25 \times 10 + 240 \times 260 \times 1390 \times 120 + 360 \times 14 + 125 \times 120 - 375 \times 7.0 - 60 \times 12.0}{2070} = \frac{19270}{2070} = \frac{9.30 \text{ IN}}{2070}$$

$$I_{m}|_{\gamma\gamma} = \frac{1}{37.2} \left[245 (634)^{2} + 25 (41)^{2} + 60 (12.0)^{2} + 375 (1.0)^{2} + 350 (12)^{2} + 290 (18)^{2} + 125 (25)^{2} + \frac{360}{12} (144)^{2} + 360 (33)^{2} + \frac{240}{12} (190)^{2} + 240 (31.5)^{2} \right] \frac{1}{144} = \frac{3.012 \times 10^{6}}{32.2 \times 144}$$


FORM 118 - (5-67)

0

PREPARED	400	1/31/73	ITT Gilfillan Inc.	SHEET 8 OF
CHECKED			PROPERTIE TRACEING	SKETCH NO.
APPROVED			STEUCTURES ANALYSIS	

STRUCTURES ANALYSIS

מאס מטושי



TORBUE LOAD

Tul = 590,0 FT-#

TORQUE BOX-BEAM ANALYSIS

REF P(1) LET SERVE TORQUE TUBE \$ 25% OF MECH. ERROR (Em)

TOTAL TORQUE LOAD ON TUBE


Tr = Ima+Tul = 0.70x650+ 590.0

TT = 1045.0 FT -# MAXIMUM TORQUE RED'O, AT AUTHORING

TORSIONAL STIPFNESS (K) OF TUBE

$$K = \frac{2t b^2 a^2}{(a+b)} = \frac{21.25(24)^2(32)^2}{(24+32)}$$

K = 5266.0 14



1

3

3

0

3

13

0

FORM 118 - (5-67)

PREPARED	APD	131/23	TTT Gilfillan Inc.	SHEET 9 OF
Trait o			" PEDJECTILE TEACKING	SKETCH NO.
CHECKED			RADAR	
			ETRUCTURES MALYSIS	

TORONE BOX- BEAM MIACLEIS (CONT, D)

SOLVE FOR MIRULAR TWIST " DEL"

ELE - Att = 0.075 x10 RAD = 0.075 M.E. KEH = . 125 OK

BENDING DEFLECTION & ROTATION OF TUBE


CONSIDER TUBE CANTILEVERED @ 3-3
UNIFORMLY LONDED W= 6= 410

$$\Delta_{T} = \frac{WL^{3}}{8EI_{vy}} = \frac{410(120)^{3}}{8\pi0^{7}k?600}$$

4 = 0.0032 IN

AMEULAR ROTATION Ab

Eb = 0.035 M.R.



Ixx = 2800 144

TILTING SCREW ACTUATOR ANALYSIS

THE ACTUATOR WILL BE A DUFF-LORTON

SEREN ACTUATOR MODEL # 1810 ARTED

AT 10 TON, THE LIFTING SCREW IS

A 2:00 INCH DIA. WITH A .50 WOU

PITCH SQUARE THEBON. THE ERECTED


LEWRITH OF THE SCREW IS

Left = 19.50 inches

CALCULATE LOADS ON ACTUATOR & TRUMBIOUS

FORM 118 - (5-67)

0



* BROSD ON THESE CALCULATED LOADS ON TRUNION EACTUATOR, STOWNEE BASS ARE RESULTED DURING RAIL ROAD *

PREPARED	4275	צרוינוי	III Gilfillan Inc.	SHEET OF
CHECKED			RADAR TRACKINA	SKETCH NO.
APPROVED			STEUCTURES ANALYSIS	

SCREW ACTUATOR ELONGATION OR CONTRACTION

ACTUATOR SCREW, EQUARE PHONO

O


0

0

0

0

ANGULAR ERROR (Ext) ELEVATION)



CHECK BUCKLING


$$\frac{\text{Prop Buckers G}}{\text{Consider Screw Length Fixed at one who }} = \frac{D_2}{4} = 1.612/4 = .403$$

$$\frac{P_{\text{Ce}}}{4} = \frac{13.141 \times 29110 \times 205}{4 \left(\frac{413}{403}\right)^2} = \frac{62,600 \text{ LBS}}{4 \left(\frac{413}{403}\right)^2} = \frac{62,600 \text{ LBS}}{4 \left(\frac{413}{403}\right)^2} = \frac{62}{4} = \frac{62}{4}$$

BEARING ANGULAR BOTATION (ELD) (EBEG)

FORM 118 - (5-67)


	S Zei	1/4/13	TIT Gilfillan Inc.	SHEET /2 OF :
СифСиф			"" ARBAT COMBINED STRUCTURAL LOADING	SKETCH NO.
APPROVED			STRUCTURAL LEAGINES	THASE 2




JOINT LOADS DUE TO ACCELERATION
$$\propto ...7 \text{ rod/sec}^2$$
 $F = ma : \frac{W}{5} r \propto - ...02174 W r$
 $F_i = \left[W r + (25 +11.7) \frac{A}{2} \right] 52 \frac{302174}{12} = \left[107 \left(54 \right) + 17.5 \left(...5 \right) 52 \right] \frac{520}{12} = \frac{13.6}{12}$
 $F_i = 19.2 \left(\frac{3}{2} \right) \frac{62174}{12} | 52 = \frac{5.4}{12} | 68 : 3.58$
 $F_i = 19.2 \left(\frac{3}{2} \right) \frac{502174}{12} | 68 : 3.58$

FORM 118 - (8-67)

PREPARED	3. 20E	7/25/13	III Gilfillan Inc.	SHEET 13 OF
CHECKED			COMPUTER MODEL FOR	SKETCH NO.
APPROVED			STRUPAK ANALYSIS	PHASE 18






ASSUME CENTER SECTION TORQUE BOX TO

BE RIGHT & DEFLECTIONS ARE DUE TO BENDING

OF TRUSS STRUCTURE ONLY



FORM 116 - (8-67)

PREPARED	TOD	2 173	TIT Gilfillan Inc.	SHEET 15 OF
Сиесия			RADAR	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

ANTENNA VEHICLE STRUCTURES MUNLYSIS


INTRODUCTION: THE ANTOUNA PETESTAL ASSEMBLY WEIGHING APPROX. 3000 LES WILL BE MOUNTED PRINCIPLY TO THE CENTER TRAILED CHASSIS AS SHOWN BELOW, POUR (4) MAIN JACKS WILL RAISE THE SPRING MASS OF THE AUTEUNA VEHICLE ASSEMBLY. A FIFTH JACK FOR PODED STABILITY IS LOCATED AT AT THE TAIL END OF TRAILER.

THE DESIGN CRITERIA IS A ROTATIONAL OR A BENDING AUGULAR DEVIATION OF

Eith) = 0.25 MILLI RADIAN (REF. SHT 1)

0

3




PREPARED	APD	21173	III Gilfillan Inc.	SHEET 16 OF
CHECKED			PROJECTILE TRACKING RADAR STRUCTURES ANALYSIS	SKETCH NO.
APPROVED				

ANTENNA-VEHICLE STENCTURES ANALYSIS (CONT. D)

ANALYSIS PARAMETHES

CHASSIS TRANSVERSE BEAM STIFFLESS DETERMINATION

 $M_{0} = F_{0} \times C_{0} / 2 = 410 \times \frac{96}{2} = 19,680 \text{ in -4 / 3eam}$ $\Phi_{0} = \frac{19,680 \times 84}{12 \text{ EI}} = \frac{19,680 \times 84}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 10^{-3} \times 30 \times 10^{6}} = \frac{18.40 \text{ in}^{4}}{12 \times 10^{-3} \times 10^{-3} \times 10^{-3}} = \frac{10.40 \text{ in}^{4}}{12 \times 10^{-3} \times 10^{-3} \times 10^{-3}} = \frac{10.40 \text{ in}^{4}}{12 \times 10^{-3}} = \frac{10.40 \text{ in}^{4}$



PREPARED	YANG	2/1/73	III Gilfillan Inc.	SHEET 14 OF
			" PROJECTILE TRACKING	SKETCH NO.
CHECKED			RADAR	
APPROVED			STRUCTURES ANALYSIS	


FRONT TRUNUION PLUOT ANDLYSIS

THE TOUNIONS ARE DESIGNED FOR. LOADS UNDER PAILROAD IMPACT LOAD. THE LOAD PER TRUNNION (REF. SHORT 10) WAS PERVIOUSLY CALCULATED TO BE

Rp = 73,000 LBS


PRE-LIMIUAR' DESIGN

Dp= 1.50 IN FEL BASIC PIN DIAMETER Left= 2.00 IN BRG. LENGTH RP ABRG = 3,00 IN2



(1806 = Rp = 73,000 = 24,300 PSi


FOR GOGI-TO CLEVIS BLOCK



BENDING STRESS ON BOLT

ASSUMED UNIFORMLY DISTRIBUTED TUBO ON Z.OO IN SPAN 1/4 IN BOLT

$$5_6 = \frac{\pi D_0}{32.0} = \frac{3.14 (1.25)^3}{32.0}$$



LECC = 2.00


0

3

2

3

0



FORM 118 - (5-67)


PREPARED	APD	2/1/73	III Gilfillan Inc.	SHEET 17 OF
CHECKED			PROJECTILE TISACKINE	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

ANTENNA-VEHICLE STRUCTURES AWALYSIS

CHABSIS TRANSVERSE BEAM (COUT'D)

ASSUMED CONC. AT CENTER

$$M_{DL} = 1500 \times 84/4 = 31,500 \text{ IN-4}$$
 $M_{LL} = F_{S} e_{C/2} = 147,000 \text{ IN-4}$
 $M_{T} = 178,500 \text{ IN-4}$
 $M_{T} = 178,500 \times 3.0$
 $M_{T} = 178,500 \times 3.0$



DYNAMIC LONDING ON FRAME

FORM 118 - (8-67)

0


0

0

0

21173		SHEET 8 OF
	THE PROJECTILE TRACKING	SKETCH NO.
	RADAR	
	STRUCTURES ANDLYSIS	
		RADAC

JACK STRUCTURE TORSIONAL & BENDING ROTATION



3

JACK SHORE REACTION (Fix) (OPERATION CONDITION)

CHASSIS TRANSUERSE BEAM (A-8) WAS PREMOUSLY SIZED TO BE GXG x 3/8 AISC TURING.


SOLVE FOR TORSIONAL STIFFNESS OF LENGTH (Lih)

FORM 118 - (8-67)

PREPARED	LPD	2173	I'I' Gilfillan Inc.	SHEET 19 OF
CHRCKED			PROJECTILE TEACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

JACK STELLCTURES TOSSIONAL & BELLANG ROTATION (CONT'D)

CONSIDER ONE JACK SUPPORT



$$\frac{\Delta_{L_{j+}}}{(I=40.5 \text{ m}^4)} = \frac{F_{j+} L_{j+}^3}{3EI} = \frac{75.0 (12)^3}{3\times30\times10^6\times40.5} = \frac{.00003 \text{ m}}{3\times30\times10^6\times40.5} = \frac{.00003 \text{ m}}{3\times30\times10^6\times31.8} = \frac{.00003 \text{ m$$

MILLIERDAN « E =0.25 $(E_{j+h}) = \frac{.00249}{84/2} \times 1000 = 0.059$

FROM THE ABOVE RESULTS A DAMETRAL CLEARANCE (SLOP) OF THE JACK CAU BE TOLERATED TO A MAXIMUM OF

PREPARED	APD	2 173	TTT Gilfillan Inc.	MEET ZO OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

3

3

ANTENNA-VEHICLE SYSTEM STABILITY - SURVIVAL COND.

P. 15 AND TAKING MOMENT ABOUT (P-P)

FS = 3070.0LBS

Cp = 120.00 IN

WAUT-PED = 3000 LBS

WTEARC = 10,000 LOS

RESTRAINING MOMENT (PM)

RM = (WA-P + WTE+AC) LAGY2

= 13,000 ×42

RM = 546,000 IN-# = 45,500 FT-#

OUESTURNING MOMENT - (OM)

OM = FS + EP

= 3070 x 120

OM = 368,400 IN-# = 30,700 FT-#

 $\frac{PM}{OM} = \frac{546,000}{368,400} = 1.48$

FOR A 13,000 LB ANTENNA-VEHICLE WEIRHT THE SYSTEM THESEFORE IS STABLE AND NEEDS HO EXTERNAL STOWAGE PROVISION.

PREPARED	APO	21173	III Gilfillan Inc.	SHEET 21 OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

F =3070

JACK PAD BERRING LOAD FWALTSIS

* USE SURVIVAL LOAD (FS) ON AUTEUNA ZMR =0

$$R_2 = \frac{F_s \, C_p}{2L} - \frac{W}{4}$$

$$= \frac{3070 \, \text{xi20}}{2 \, \text{84}} - \frac{13,000}{4}$$

$$= 2190 - 3250$$

R2=-1060 LBS COMPRESION ON SOIL

EMPL = 0

0

R = - 5440 LBS COMPRESSION

DESIGN JACK PAD FOOT PRINT BASE
ON MAX, OPERATING BEARING LOND OF * Para = 5000 LBS

* DESIGN JACK FOR STON OR 10,000 LAS CAPACITY

-W = 13,000 &

ASSUMPTION

OUSE MODIUS OF SUBFRADE ROACTION Ky = 100 PSI/IN GILET MAXIMUM BEG. LOND) = 1500 FOF - WHICH WILL ALLOW THE SYSTEM TO OPERATE ON SOIL SUCH AS SOFT CLAY, CLAY LOAM, POORLY COMPACTED SAND, CLAY CONTAINING LABRE AMOUNT OF SILT & WATER STANDS DURING WET SEASON!

FORM 118 - (8-67)

races .	B. ROE	10/5/16	ITT Gilfillan	SHEET / OF /
CHECKED			PHASE B ANTENNA	SKETCH NO.
APPROVED			WEIGHTS	

ANTENNA STRUCTURE	722.0
LINE FEED	45.5
ARRAYS (167)	235.5
MONITOR LINE	22.4
PHASE SHIFTERS (167)	167.0
PHASE SHIFTER HOUSING	45.3
CAMBS	26.0
	1263.7 16

WEIGHT OF ANTENNA SYSTEM DESIGNED &

FABRICATED UNDER PHASE & THESE WEIGHTS

WILL BE UTILIZED IN PHASE C FOR

ANALYSIS & DESIGN OF SERVE SRIVE SYSTEM.

REPORT DISTRIBUTION

Required Distribution	Number of Copies Reports
	Final Tech Report DI-S-180
Commander	
Picatinny Arsenal	
ATTN:	
Technical Support Directorate	
SARPA-TS-T-S	5
SARPA-TS-1	1
Product Assurance Directorate SARPA-QA-A-R	10
Dover, New Jersey 07801	
Project Manager	
Munitions Prod Base	
Mod & Exp	
Picatinny Arsenal	
ATTN:	
DRCPM-PBM	1
Dover, New Jersey 07801	
Defense Documentation Center	
Cameron Station	
Alexandria, Virginia 22314	12
Commander	
U. S. Army Material Development &	
Readiness Command	
ATTN:	
DRCRD-WC	1
DRCRD-OS	1
DRCQA-E	1
Washington, D. C. 20315	
Commander	
U. S. Army Armament Command	
ATTN:	
DRSAR-QAE	3
DRSAR-RD	1
DRSAR-AS	1
Rock Island, Illinois 61201	

U. S. Army Electronics Command ATTN: DRSEL-CT-R Fort Monmouth, N.J. 07703	3
Commander	
U. S. Army Test & Eval. Command ATTN:	
DRSTE-RU Aberdeen, Maryland 21005	1
Commander	
U. S. Army Missile Command ATTN:	
Technical Library	1
Redstone Arsenal, Alabama 35809	
Commander	
Ballistic Research Laboratories ATTN:	
Technical Library	1
Aberdeen Proving Ground	
Maryland 21005	
Commander	
Harry Diamond Laboratories ATTN:	
DRXDO-TA	1
Washington, D. C. 20438	
Commander	
Frankford Arsenal	
ATTN:	
N3200	1
Philadelphia, PA. 19137	
Commander	
Aberdeen Proving Ground	
ATTN:	
STEAP-MT-G	1
Aberdeen Proving Ground, Maryland 21005	
Commander	
Yuma Proving Ground ATTN:	
STEYP-MTS	1
Vuma Artanna 85624	

Commander	
White Sands Missile Range	
ATTN:	
Technical Library	1
New Mexico 88002	
Commander	
Jefferson Proving Ground	
ATTN:	
STEJP-MTM	1
Madison, Indiana 47521	
Commander	
Naval Ordnance Systems Command	
ATTN:	
Code ORD-0462D	1
Washington, D. C. 20362	
Director	
Naval Research Laboratories ATTN:	
Technical Library	
Washington, D. C. 20390	1
washington, D. C. 20390	
Commander	
U. S. Naval Weapons Laboratory	
ATTN:	
Technical Library	1
Dahlgren, Virginia 22488	
Commander	
U. S. Naval Ordnance Test Station	
ATTN:	
Technical Library	1
China Lake, California 93555	
Commander Marine Corps	
Hq., U. S. Marine Corps	
ATTN:	
Code A04C	1
Washington, D. C. 20380	
Commander	
Wright Air Development Division	
Wright-Patterson Air Force Base ATTN:	
Technical Library Ohio 45433	. 1
UNITO 43433	

Commander
Rome Air Development Command
Griffiss Air Force Base
ATTN:
Technical Library
New York 13440
Commander
Air Force Rocket Propulsion Lab (AFSC)
ATTN:
Mr. L. Meyers (RPMMA)
Edwards Air Force Base
California 93523
Carriornia 75725
Commander
ADTC (ADLEG)
ATTN:
Mr. J. Howanick
Eglin Air Force Base
Florida 32542
11011da 32342
Commander
Service Engineering Division (MME)
ATTN:
Mr. D. Hebdon (MMECL)
Hill Air Force Base, Utah 84401
사용 어느 사용 아이스 학생들은 아이들이 가는 사용을 하는 것이 되었다면 하는데 하는데 하는데 하는데 하는데 그는 것이 되었다면 하는데 하는데 얼마를 하는데

UNCLASSIFIED SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered) **READ INSTRUCTIONS** REPORT DOCUMENTATION PAGE BEFORE COMPLETING FORM 2. GOVT ACCESSION NO. 3. RECIPIENT'S CATALOG NUMBER TYPE OF REPORT & PERIOD COVERED TITL TE-Application Of Radar To Ballistic Accep-Final Report tance Testing of Ammunition (ARBAT). PERFORMING ORG. REPORT NUMBER Phase B: Antenna Development/Fabrication 50594 7. AUTHOR(e) CONTRACT OR GRANT NUMBER(#) C. Barfield DAAA21-73-C-Ø664 PERFORMING ORGANIZATION NAME AND ADDRESS International Telephone & Telegraph Corporation Gilfillan Division MM&TE Project 5704139 7821 Orion Street, Van Nuys, CA. 91409 11. CONTROLLING OFFICE NAME AND ADDRESS REPORT DATE 30 Sep 07801 Picatinny Arsenal, Dover, N.J. 14. MONITORING AGENCY NAME & ADDRESS(II different from Controlling Office) Unclassified 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A 16. DISTRIBUTION STATEMENT (of this Report) Unlimited 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, If different from Report) 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Antenna Performance Monitor Ammunition Testing Phase/Frequency/Mechanical Scanning Ballistic Trajectory Electronic Elevation Scanning Low Sidelobe Amplitude Dual Slot Radiators Planar Array Antenna Projectile Tracking Radar ABSTRACT (Continue on reverse side if necessary and identify by block number)

Antenna design analyses performed in an earlier program phase (ARBAT System Design Study) were validated and used in the final development and fabrication of an "X" band phase/frequency mechanical scanning radar antenna to be incorporated in a radar system for ballistic ammunition acceptance testing. The antenna is a 10 by 12 ft aperture planar array. Elevation scanning is accomplished by phase changes produced by digitally controlled 4 bit diode phase shifters. Scanning in azimuth is by frequency variation and mechanical

DD FORM 1473 EDITION OF I NOV 65 IS OBSOLETE

0

0

0

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entere

SECURITY CLATTICATION OF THIS PAGE(The Date Extend

Block No. 20 (Continued)

rotation of the array. Development steps included fabrication and testing of individual critical items and assemblies of critical items to estimate full array performance. A 9 element partial array was range tested prior to fabrication of the required 167 horizontal array elements and associated microwave elements. The mechanical and electrical design is discussed and test results are summarized.

UNCLASSIFIED